



City of Atlanta Mayor Kasim Reed

Department of Watershed Management

Southeast Atlanta Green Infrastructure Initiative: Permeable Paver Roadways

Cory Rayburn, CPESC, CFM, EnvSP Construction Project Manager

SESWA Spring Seminar April 15, 2016

Background

- City's Department of Watershed Management
 - Serves 1.2 million (450,000 night)
- Consent Decree
 - CSO completed 2008
 - SSO extension granted 2027
- 2nd highest W&S rates in the country
- Stormwater Utility Fee
 - Adopted in 1999
 - Overturned \$7 million refunded







Custer CSO Basin Location



 Heart of Atlanta
Highly impervious
Dipod Streams

- Piped Streams
- Repeated Flooding

Rank	Date	Recurrence Level
1	7/9/2012	10-25 year
2	8/31/2006	5-10 year
3	7/11/2012	2-5 year
4	9/29/2009	2-5 year
5	7/3/2012	2-5 year
6	5/5/2003	2-5 year
7	7/20/2011	2 year
8	8/20/2000	2 year
9	6/3/2001	2 year
10	8/28/2009	2 year

Contributing Conditions



Drainage Basin	Total Area (acres)	% Impervious	Impervious Area (acres)	Roadway Area (acres)
Mechanicsville / Peoplestown	900	65%	582	220
Summerhill	505	58%	293	110
Grant Park	380	42%	162	55
Englewood Manor	715	42%	301	62





Mayor's Commitment to the Community

- Assessment of drainage/capacity issues
 - Caused by capacity limits in the combined sewer system (CSS)
 - Multiple areas affected; Peoplestown, Summerhill, and Mechanicsville
- Long-term solution to reduce flooding
 - Assessment of issues
 - Phased approach
 - Follow-up community meetings





Assessment of Issues

Exceed capacity in the Combined Sewer System



Overview of Solutions - Phased Approach

- Immediate Response Completed
 - Catch basin & inlet cleaning
 - Raising curbs
- Phase 1 Projects Completed
 - Green Infrastructure Projects (bioswales, rain gardens, revegetation)
- Phase 2 Projects
 - Media Lot CSS storage vault Completed
 - Permeable pavers Under Construction
- Phase 3 Projects In progress
 - Connally Trunks CSS storage vaults
 - Capacity Relief Project



Immediate Response

Begin tangible solutions in 30 days



Phase 1 Projects- Completed

Use of Green Infrastructure; mimics nature

Southeast Atlanta Green Infrastructure Initiative Phase 1 - Peoplestown, Mechanicsville and Summerhill

Completed Sites



Phase 2 Project – Media Lot Vault Completed



Phase 2 Project – Pavers Under Construction

Approximately 6 miles Permeable Pavers



Construction Sequence

- Excavation
- Aggregate reservoir
- Paver Installation



General Challenges

- Utilities (water, sewer, gas, etc.)
- GDOT
- Road Closures & MARTA



Notable Challenges

Concrete wash-off, sedimentation from adjacent development, utility tie-in protocols, & historic street car tracks



Ideal roadway paver shape and configuration – L-shaped bricks selected



Steep slopes - impermeable liner check dams used



Roads designed to maintain crown



Vegetated Stormwater Planters in conjunction with pavers



Monitoring efforts

Underdrain flow monitoring and infiltration wells



Community Outreach Efforts

 Road closures, utilities affected, temporary access, sanitation pickup, etc.



All in all...

Overall Success



Effectiveness (25 Yr - 4 Hr Storm) – 3.86" rainfall

 Model simulation indicates flood reduction but not elimination of localized flooding





Phase 3 Projects – Design Phase

Additional capacity relief needed for localized flooding



Peoplestown Capacity Relief Ponds

- Detention ponds & Bioretention provides 2MG of storage
- Provides a controlled area for combined sewer spill containment
- Provide aesthetic and passive recreational enhancement



Questions? www.AtlantaWatershed.org/GreenInfrastructure



Cory Rayburn, CPESC, CFM, EnvSP City Of Atlanta | Department of Watershed Management <u>CRayburn@AtlantaGA.gov</u>