

Don't Take Grants for Granted

Leveraging the Most from
Congressional Funding
Opportunities for the Life-Cycle
Overhaul of an Inventory of
Municipally Operated Dams

James Grimes, PE
Brandon Harris, PE



Gwinnett



Presentation Outline

- What is ARPA?
- Dams Program at Gwinnett County
- Project Scoping Process
- Resulting Scope/Project Delivery
- Status of ARPA Funded Projects
- Lessons Learned

What is ARPA?

American Rescue Plan Act

- What is it?
 - Congressional allocation from H.R.1319 - American Rescue Plan Act of 2021 117th Congress
 - Coronavirus State and Local Fiscal Recovery Funds
 - 181.9M awarded county-wide to Gwinnett
 - 10M utilized for dam infrastructure

GCID 2021-1192
9.21.2021

Gwinnett
American Rescue Plan Act (ARPA)
Coronavirus State and Local Fiscal Recovery Funds

Project	Amount
Support Public Health Response	\$181,958,521
COVID-19 Public Health Response	\$4,837,500
Vaccination, COVID Testing/Tracing, etc.	\$500,000
Vaccine Education & Outreach	\$476,000
Mass Vaccination Site Facility Maintenance & Operations (through 12.31.2022)	\$6,105,788
Eastside Vaccination Site Operations (through 12.31.2022)	\$250,000
Vaccination Incentive Program (\$100 gift cards, est. 2,500 served)	\$1,050,000
Public Health Infrastructure & Equipment Enhancements	\$2,050,000
Mobile Clinic Expansion Project	\$1,000,000
Mental Health & Substance Abuse Crisis Services	\$1,000,000
Replace Public Sector Revenue Loss	\$28,000,000
Government Services Affected by Revenue Reduction	\$28,000,000
Equity-Focused Services	\$61,160,800
Facility & Service Provisions	\$25,000,000
Centerville One Stop	\$30,000,000
Gwinnett One Stop	\$435,800
Veteran Support Services	\$5,000,000
Nonprofit Services - Target Areas	\$350,000
Systems Needs Assessment	\$375,000
Outreach & Training Services	\$375,000
Address Negative Economic Impacts	\$28,947,500
Rebuilding Tourism, Arts & Entertainment	\$2,000,000
Small Business Recovery & Restart Program	\$5,000,000
Workforce Development	\$500,000
Youth Engagement	\$500,000
Job Training & Development	\$5,000,000
Nonprofit Capacity Building & Operating Support	\$500,000
Childcare Services	\$1,214,000
Food Insecurity	\$500,000
Early Childhood Learning & Literacy	\$500,000
Transportation Services	\$500,000
Other Gwinnett County Government Operational Needs	\$20,000,000
Technology Enhancements	\$1,850,000
Tax Commissioner Convenience Fees Waiver Program	\$800,000
Community Navigator Program	\$300,000
Enhanced Cleaning Services	\$100,000
Public Facility Enhancements	\$76,500
Equipment - Titan Modems for Cardiac Monitors	\$40,000
Equipment - Forklifts for PPE Distribution	\$45,000
Branch Security Costs - Tax Commissioner	\$65,000

Essential Workers

Program	Amount
Premium Pay & Recruitment Incentives for Essential County Workers	\$11,651,964
Pass-through Incentives to Vendors Providing Critical County Services	\$300,000
Hazard Pay (Paid out to County employees 1.1.2021 - 6.11.2021)	\$150,000
Infrastructure	\$11,299,964
Septic to Sewer Conversion Program	\$14,000,000
Dam Rehabilitation Projects	\$2,000,000
Home Repairs Assistance Program	\$10,000,000
Broadband Enhancements (OCT Areas)	\$2,000,000
Future Need	\$5,000,000
Future Need	\$5,818,035

What is ARPA?

American Rescue Plan Act

- **Use it or Lose It!**

- Stipulations from the Federal Government for use of Funds
- Must be allocated/encumbered under contract by December 2024
- All funds spent/done with construction by December 2026
- We hit the ground running 2022 – 2023 sourcing projects



Dams Program at Gwinnett

Program Overview

Program Goals

- Ensure compliance with GA DNR/EPD Safe Dams Program guidelines and regulations
- Maintain safe operating conditions at all Gwinnett maintained dam sites
- Safeguard public lives and infrastructure from flood damage
- Technical resource to citizens and Gwinnett Office of Emergency Management

Approach to Projects

Projects identified through a continuous monitoring, regulatory inspection program, and life-cycle condition assessments.

- Improvement projects proactively correct any deficiencies in conditions of dams, in areas of personnel and public safety
- Dam Rehabilitation: replacement of major components in response to watershed changes or dam reclassification by regulatory agencies requiring spillway capacity upgrades, embankment overhauls etc.
- Dam Maintenance: aimed at extending service-life of dam components, providing safe operating conditions/access during inspections or emergency conditions, and returning dam to intended design state
- Dam Removal/Decommission: removal of structure if dictated by engineering, fiscal, or safety concerns

Dams Program at Gwinnett

Inventory of Structures



Dams Program at Gwinnett

Inventory of Structures



Project Scoping Process

Beginning with Project Drivers



Flood Retention

Continued design function



Extend Service-Life

50-yr intended design life of NRCS dams
Presently year 57+ for dams installed as early as 1967. Issues can be addressed by projects to extend service-life by another 20-yr



Public Health and Safety

Well maintained high hazard structure limits risks to public and infrastructure downstream



Compliance

With state and federal agencies as an operator and facility co-sponsor



Gwinnett



Project Scoping Process

Determining Spheres of Influence

Influence per Dam Characteristics

Height	40 ft
Drainage Area	1,990 Acres
Storage Volume Behind Dam	1485 Acre-feet

Utility Infrastructure at Risk in Breach Zone


Water Pressurized Main	2.71 miles of pipe in breach
Stormwater Closed Conduit	3.07 miles of pipe
Sewer	2.16 miles of pipe
Roadway	4.16 miles of roadway

Critical Infrastructure in Breach Area

Hospitals	0 Known
Schools	0 Known
Police/Fire Station	0 Known

Population at Risks in Breach Zone (Category-1/High Hazard)


Parcels	616 affected
Development Areas	49 Community/Development areas affected
Houses	60 at risk
Hospitals	0
Schools	0
Parks	1 in breach zone



Project Scoping Process

Continuing with Existing Conditions Assessment and Asset Evaluation


- **Mining** existing as-builts and **Record Documents** for intended design state
- **Mining** quarterly visual inspections for **Persistent Maintenance Issues** requiring heavy construction or heavy landscaping
- **Detailed Visual Inspections (VIR)** of dam embankments and outer facets by GA Safe Dams Engineer-of-Record
- **Structural Concrete Condition Assessments**
 - **Underwater Diving Inspections** of risers/outlet control structures
 - **PACP CCTV Analysis** of Principal Spillway Conduits through dams
- **Mechanical Condition Assessment** of low-level gates, valve casings, and stems



Existing Conditions & Assessment




Existing Conditions & Assessment



4 Corrugated steel likely used as cover/trash barrier for overflow opening. Showing extreme corrosion and section loss.



1 Horizontal angle-iron anchored to the concrete via J-Bolts. Angle-iron and J-Bolt both showing evidence of heavy corrosion.




2 Stainless steel valve stem coupler showing 1 of 4 attachment pins.



3 Wild life gate guides showing heavy corrosion. Guide off set anchors also showing heavy corrosion.

Existing Conditions & Assessment



1




2



3



4



Condition Matrixing

Dam ID	Gate(s)	Low-Stage Trash Rack	High-Stage Trash Racks	OCS Structure	PSP Outlet	PSP Interior	Safety ¹	Notes
Phase 1 Inspections								
M-7 ²	P	P	F	P	F	F ³	U	LL gate is leaking; WL gate is inoperable but is not emergency since LL gate is operable.
H-21	P	N/A	P	P/FO	F	F	U	Gate is intact but has heavy corrosion. OCS has high submergence and high "clog-ability".
H-22	P	P	S/F	P	F	F/P	U	Successful rehabilitation of gate is not likely.
TM-1	S/F	P	P	F/P	F	F	U	Cracks and exposed reinforcement in slab. Wildlife gate is in satisfactory condition.
TM-2	F/P	P	P	P	P	P ³	U	Poorly constructed overall. Low-level gate is in fair condition.
Y-14	P	P	S/F	F/P	F	F/P ³	U	Gate stem bent. Gate has heavy corrosion.
Y-15	P	N/A	P	P/FO	F	P ³	U	Longitudinal cracks in PSP. OCS has high submergence and high "clog-ability".
Phase 2 Inspections								
M-11 ²	P	N/A	F	F	F	F/P	U	Interior inspection was postponed due to high water.
H-3	P	F	F	P	S/F	P	U	Low-stage trash rack was replaced.
H-25	P	P	F	P	F	F/P	U	Gate was sealed but had more corrosion than most.
N-1	P	P	S/F	P	P	F	U	Leaking gate.
Inverness	S	N/A	F/P	F/P	F	F	S	Most of OCS was fair but the joints were poor.
Y-3	P	P	F/P	P	F/P	P	U	Leaking gate. High-stage trash rack members were fair, but the hardware was poor.
Y-16	F	F/P	F	P	P	F/P ³	U	Gate replacement is recommended, but the gate was in better condition than most.

Satisfactory/Fair

Satisfactory

Fair

Fair/Poor

Poor/Functionally
Obsolete

Unsatisfactory

Scope Recommendations Common to all Site

Riser	Impact/Stilling Basin(s)	Embankment	Spillway
<ul style="list-style-type: none">○ Full in-kind replacement or Upgrades of riser structure (OCS)○ Updated wildlife gate, corruptions resistant trash rack○ Access and Safety Improvement (ex: access ladder and safety railings)○ Reduce likelihood of platform and valve inundation○ Addition of public caution signage	<ul style="list-style-type: none">○ Replacing impact basin baffle block○ Replace top slab extension○ concrete point-repairs and riprap replenishment○ Replace animal guards○ Replenish Riprap Apron	<ul style="list-style-type: none">○ Slope Refurbishment○ Create buffer zone between toe of dam and encroaching tree line per maintenance standards	<p>Lining Principal Spillway Pipe (PSP)</p>

Project Delivery

Project Scope

Remove unwanted vegetation from dam limits




Y-15 Dam, pre and post removal of unwanted vegetation (2023)

Project Delivery

Project Scope

Replace or repair outlet control structures





H-22 Dam Outlet Control Structure, Structural Inspection Report (2019) and Design Drawings (2023), Stantec

Project Delivery

Project Scope

Line principal spillway pipes (Cast in Place Pipe lining)




H-22 Dam CCTV Inspection conducted by GCDWR (2019), Annotations by Stantec (2019)

Project Scoping Process


Short-listing and contingency planning

Ranking Based On Condition Matrix



2	N-1	Replace Gate, Repair Structure, Add Remote Actuator
	TM-1	Replace Gate, Repair Structure
	Y-3	Replace Gate, Repair Structure, Add Platform, Line PSP
	Y-14	Replace Gate, Repair Structure, Add Platform, Line PSP
	Y-16	Replace Gate, Repair Structure, Line PSP
3	M-11	Replace Gate, Repair Structure, Add Remote Actuator, Line PSP
4	H-21	Replace Structure
	TM-2	Replace Structure, Line PSP, Replace PSP Impact Basin
	Y-15	Replace Structure, Line PSP
	Y-17	Replace Structure, Line PSP

Ranking Based on Level-of-Effort & Costs




1	H-21	Replace Structure
2	Y-15	Replace Structure; Line PSP
3	TM-2	Replace Structure; Line PSP; Replace PSP Impact Basin
4	Y-17	Replace Structure; Line PSP
5	M-11	Replace Structure, or Replace Gate, Add Remote Actuator, and Repair Structure; Line PSP
6	H-22	Replace Gate, Repair Structure; Add Platform; Line PSP
7	Y-14	Replace Gate; Repair Structure; Add Platform; Line PSP
8	N-1	Replace Gate; Repair Structure; Add Remote Actuator
9	Y-3	Replace Gate; Repair Structure; Add Platform; Line PSP
10	M-7	Replace Gates; Repair Structure; Add Platform

Ranking Based on Compliance & Risk Drivers

 **Natural Resources Conservation Service**
U.S. DEPARTMENT OF AGRICULTURE


 **GEORGIA**
DEPARTMENT OF NATURAL RESOURCES
ENVIRONMENTAL PROTECTION DIVISION



Order	Site	Critical Task(s)
1	H-21	In-operable Gate Valve
2	H-22	In-operable Gate Valve
3	Y-15	In-operable Gate Valve
4	Y-14	Dysfunctional Gate Valve

Project Delivery

Project Development Timeline



Total timeframe between 1 – 3.5 years from finalization of scoping until award of contract

- Challenge meeting fund allocation deadline

Project Delivery


Project Development Timeline

Crashing schedule as much possible to meet ARPA deadlines

- Portions of project delivery timeline that could be shortened
 - Detailed Design (w/ buy-in from Engineer)
 - Weigh risks of accelerated design schedule
 - Specifications & Bid Package Development
 - Perform during detailed design
- Aspects out of direct control
 - Permitting
 - Regulatory entities approval and coordination (NRCS, GA DNR/Safe Dams)
 - Land acquisition and easements
 - Project advertisement and contract administrative timelines

Project Delivery

Initial Project Development Strategies



Project Delivery

Initial ARPA Projects (2021 Assumptions)

Project	Initial Engineer's Estimate
Y-15 Dam Outlet Control Structure Replacement	~\$800K
Combined Dams Outlet Control Structure Maintenance	~5.0M
TM-2 Dam Outlet Control Structure Replacement	~\$1.0M
Rhodes Jordan Dam Siphon Construction	~400K


Project Delivery

Initial Price Feedback

Y-15 Project Bids: May 2023

Combined Dams Project Bids:
August 2023

- Large cost increases observed from data utilized in cost estimate preparation (pre COVID era costs)
- Only 1 Bid received Combined Dams



Project Delivery

Bid Comparison

Bid Item	Initial Estimate Unit Price	Average Bid Unit Price
Full Lake Lowering/Dewatering	~\$100K (lump sum)	~\$500K (lump sum)
Partial Lake Lowering/Dewatering	~\$5K (lump sum)	~\$130K (lump sum)
Mobilization	~\$40K (per site)	~\$160K (per site)
CIPP Lining	~\$300 (linear foot)	~\$1000 (linear foot)

Price increases observed across the board

- Observed prices from projects ~3 years ago outdated

Project Delivery

Direct Feedback

Feedback from Combined Dams Project

Contractor Schedule Constraints

Perceived risk in water control portion of projects

Request for greater breakdown of project costs



Project Delivery Update

Break project portfolio into smaller groups

Ease project schedule constraints


Revise bid schedule strategies

Current Status

Revised OPCC Comparison

H-21 Project Bids: January 2024

- Slightly better price
- Increased bid response



Current Status

Revised ARPA Projects (Current Plan)


Project	Current Contract/Estimate
Y-15 Dam Outlet Control Structure Replacement	Finalized contract \$2.0M
H-21 Dam Outlet Control Structure Maintenance	Finalized contract \$1.2M
H-3, H-22, and H-25 Dams Outlet Control Structure Maintenance	Contract to be finalized July 2024
Y-14 Dam Spillway Maintenance	Currently Out for Bid

Current Status

Construction Schedules


Individual project timeframes under 1 year

- Understand potential for material procurement delays



Current Status

Project Schedules



Gwinnett County DWR on track to utilize full amount of ARPA grant money allocated for dams projects

Conclusions

Lessons learned for successful utilization of grant funds:

- Maintain capability and knowledge base necessary to obtain grant funds
- Know the current needs of your stormwater systems before you are under grant schedule constraints
- Understand the challenges presented by grant utilization criteria
- Be ready to expedite portions of project delivery
- Be flexible with project delivery strategies
- Utilize all available feedback to improve project delivery processes

Thank You!



James Grimes, PE

Gwinnett County - Department of Water Resources
Engineer V, Engineering and Construction Stormwater Group

Mr. Grimes is a civil engineering professional with over 13 years experience in the analysis, design, and operation of dams and stormwater systems. He holds a bachelor's degree in civil engineering from Georgia Tech and a master's degree in environmental engineering from the Hamburg Technical University.



Brandon Harris, PE

Gwinnett County - Department of Water Resources
Dams Program Manager - Stormwater Technical Services

Mr. Harris is a civil engineering professional with over 15 years experience in project management, H&H modeling, CFD, statistical data analysis, stormwater infrastructure design, inspection of dams, emergency response, and program management of stormwater municipal assets. He holds a bachelor's degree in Civil & Environmental Engineering from Georgia Tech.

